



SAL5-V4-3/15/21
 Date: 2/18/2025
 Company: City of Laredo
 Attn: Joel Vazquez
 Program Name: Laredo Tourism Van
 Job #: TBD

Laredo Tourism Van- GSA Contract #47QMCA21D000U

Unit Price

Unit Total

1	Vehicle- CGS to provide a new high roof Ford Transit Van and prep the unit for the buildout.		
2	Interior Finish- Along the passenger side wall only CGS to install plywood with white enamel installed on surface. Over the enamel we will install metal grating for brochure holders. The other interior walls, ceiling and floor will be left the same material		
3	Windows- CGS to cut out 2 windows along the driver side of the vehicle and reinforce as needed. One of the openings will be used for a shadow box where CGS will install a customer supplied television with the other window being an area for people to interact with staff. Both of the windows will have an aluminum flip up door on shocks.		
4	Electrical- Installation of wiring for the TV and LED lighting interior lighting that will be installed. The electrical will be run off of the transit battery.		
5	Graphics- CGS to set-up, print, finish, and install show quality Avery Graphics wrap on the exterior of the van. Graphics tucked and layered where required. Choice of matte, gloss or luster laminate.		
6	Job management, Production coordination, Set up, Testing		
7	Estimating, Administration, Purchasing		
8	Overhead, Insurance, Training, Tech support and Templates		
	Base Total		\$113,900.00
	Approved Options		
9	Marquee- Custom fabrication of a marquee with non lit dimensional letters similar to what is on the Dallas Tourism Van.		\$11,245.00
10	Fans- CGS to supply and install 2 interior electric fans and wiring to them		\$1,970.00
11	Cabinet- CGS to provide a base 4' cabinet with two doors for storing handout and souvenirs. The cabinet will have a wood counter top.		\$2,400.00
12	Electric Actuator- CGS to provide an electric actuator for the marquee so that your team can raise and lower the marquee with a push of a button and not need to go on a ladder to lower.		\$7,450.00
13	Shorepower Inlet- CGS to provide a shorepower inlet and 1000 W inverter so that the electrical can be run off of a portable generator.		\$4,600.00
14	Additional Outlets- CGS to install 2 additional power outlets in the van.		\$950.00
15	Sound System- Supply and installation of an exterior sound system. The sound system will have 2 exterior mounted speakers that will need to be installed once at your event site. On the interior you will have a mixer, amplifier and a wireless microphone		\$4,800.00
	Total Estimated Cost		\$147,315.00

All sales and services are subject to the CGS Premier, Inc. Terms and Conditions

Payment terms: 50% down payment due at time of signed scope of work with the balance due upon completion (note...a delay in down payment may result in a delay in completion)

CGS to provide a detailed timeline upon the receipt of this signed scope of work outlining key dates in order to keep this project on track for an on time completion.

Pricing is valid for 7 Days

Additional elements not included in the above estimate:

- Artwork or file manipulation.
- Customer alterations or additions.
- Overtime needed to complete based on delays in the approved timeline or a change in the completion date.
- Applicable sales tax (5.1%), permitting or engineering stamps
- Shipping

Accepted By: _____

Date: _____

Thank you for this opportunity!

CGS Premier S64W15586 Commerce Center Parkway Muskego, WI 53150 Phone 262-641-7414 Fax 262-641-7420