



4010 Billy Mitchell Addison, TX 75001

(817-798-5388 Office (972) 248-2600

| | |
|--|-------------------------------------|
| To: City of Laredo, TX | From: Douglas Varner |
| Attn: Arturo Garcia --- C/O Jose Wicho Tijerina | dvarner@municipalvalve.com |
| Phone: 956-401-5886 | Pages: 1 |
| E-Mail: Agarcia@ci.laredo.tx.us ; Tjijerina@ci.laredo.tx.us | Quote Date: October 31, 2023 |
| Re: Rubber flapper check valves and gate valves | |

MVE TIPS VENDOR CONTACT #: 23010401

| QUANTITY | PRODUCT NO. | DESCRIPTION | PER UNIT VALVE PRICING | TOTAL VALVE PRICING |
|----------|-------------|---|------------------------|---------------------|
| 2 | 7218CBFMI | 18" Rubber Flapper Check Valve. AWWA C508 Class 125 Body: Ductile Iron; Disc: Buna-N; Bolts: Stainless; Disc accelerator: Stainless; with Adjustable Spring Return, Model No. RF161-ASR, Class 150# Flanged Ends, Ductile Iron Body and Cover, Steel & Nylon Reinforced Buna Rubber Flapper, Steel Bolting, Lined & Coated with 8 +/-4 Mils DFT of Tnemec 140 Epoxy,250 PSI Maximum Working Pressure: | \$ 28,448.00 | \$ 56,896.00 |
| 1 | 7224CBFMI | 24" Rubber Flapper Check Valve. AWWA C508 Class 125 Body: Ductile Iron; Disc: Buna-N; Bolts: Stainless; Disc accelerator: Stainless; with Adjustable Spring Return, Model No. RF161-ASR, Class 150# Flanged Ends, Ductile Iron Body and Cover, Steel & Nylon Reinforced Buna Rubber Flapper, Steel Bolting, Lined & Coated with 8 +/-4 Mils DFT of Tnemec 140 Epoxy,250 PSI Maximum Working Pressure: | \$ 51,185.00 | \$ 51,185.00 |
| 1 | RWGVFL30 | 30" SERIES 2638 RESILIENT WEDGE GATE VALVE, NON RISING BRONZE STEM, OPEN LEFT, FLG X FLG, AWWA C515 RATED TO 250 PSI, DUCTILE IRON BODY/BONNET, EPDM ENCAPSULATED DUCTILE IRON WEDGE, FUSION BONDED EPOXY INTERIOR & EXTERIOR, 304 SS FASTENERS. BONDED EPOXY INTERIOR AND EXTERIOR, RUST PROOF STEEL BOLTS AND NUTS, SPUR GEAR AND 2" OP NUT. | \$ 53,849.00 | \$ 53,849.00 |
| | RWGVMI36 | 36" SERIES 2638 RESILIENT WEDGE GATE VALVE, NON RISING BRONZE STEM, OPEN LEFT, FLG X FLG, AWWA C515 RATED TO 250 PSI, DUCTILE IRON BODY/BONNET, EPDM ENCAPSULATED DUCTILE IRON WEDGE, FUSION BONDED EPOXY INTERIOR & EXTERIOR, 304 SS FASTENERS. BONDED EPOXY INTERIOR AND EXTERIOR, RUST PROOF STEEL BOLTS AND NUTS, SPUR GEAR AND 2" OP NUT. | \$ 80,533.00 | \$ 80,533.00 |
| | | Total Price | \$ | 242,463.00 |
| | | Check valve Lead Time | | 24 -26 weeks |
| | | Gate valve Lead Time | | 36 -40 weeks |
| | | PrePay and Freight Estimate | | Freight Included |

Payment Terms: Net 30 Days

Prepared by: Doug Varner
dvarner@municipalvalve.com

All prices are quoted in United States Dollars, exclude applicable taxes, and are subject to credit approval.