



Midas Contractors, LLC.
2710 Zacatecas
Laredo, TX 78046

April 8, 2026

Owner: City of Laredo
Project: Concrete Road
Location: Laredo International Airport

PROPOSAL

SCOPE OF WORK:

Midas Contractors will provide all labor, material, equipment, and supervision necessary to perform the following work.

Concrete Road

- 1.- Sawcut & remove approximately 10" of existing concrete pavement, to be hauled off from site and disposed. \$ 520,000.00
- 2.- Remove existing asphalt pavement.
- 3.- Compact 8" of existing subbase soil to 95% compaction.
- 4.- Existing subbase to be proof-rolled.
- 5.- Place #5 bars at every 12" O.C. Each way with 15' construction joints, to be sealed with cedar-compatible flexible joint sealant.
- 6.- Pour 4000psi concrete in approximately 24,0700 SF to be 10" thick.
- 7.- Finish pavement to a smooth, uniform surface.
- 8.- Apply curing compound to finished concrete surface.
- 9.- Clean area and remove any debris from site.
- 10.- As per specification and plans dated 3/9/2026

Owner Contingency allowance, to be used for unforeseen circumstances \$ 25,000.00



783-25

Notes:

Laboratory testing fees included.

TOTAL: \$ 545,000.00

FIVE HUNDRED FOURTY-FIVE THOUSAND DOLLARS and 00/100

- a) Any item, job or service not mentioned in this estimate, will be consider as "NOT INCLUDED".
- b) Client must allow adequate time & space for contractor to perform the task in a professional manner.
- c) This proposal is valid for 30 days.

Sincerely,

Patricia Contreras
Midas Contractors, LLC.
(956)625-8259